

## HARWICK ROAD, YORKSHIRE ROAD AND BROCKLEY ROAD

*Irondequoit, New York*

Passero Associates provided design and construction administration services for these Town of Irondequoit street improvement projects.

The Brockley Road project consisted of installation of a storm sewer, manholes and catch basins and replacement of the sanitary sewer including new manholes, house laterals, clean outs and appurtenances. The existing pavement was reconstructed including driveway aprons, gutters, skip block sidewalk replacement, landscaping and other appurtenances.

Yorkshire Road consisted of installation of a storm sewer, manholes, catch basins and replacement of the sanitary sewer including new manholes, house laterals, clean outs and appurtenances. The existing pavement was reconstructed including driveway aprons, gutters, full length sidewalk replacement, landscaping and other appurtenances.

Harwick Road consisted of installation of driveway aprons, catch basins, gutters, skip block sidewalk replacement, landscaping and other appurtenances. The existing pavement was milled and resurfaced.

**Client:**

Town of Irondequoit

**Construction Cost:**

\$1,860,000

**Completion Date:**

December 4, 2004

**Services Provided:**

Capital Improvement Plan  
Comprehensive Plans  
Construction Administration  
Construction Inspection  
Construction Layout/  
Stakeouts  
Contract Documents  
Cost Estimating  
Highway Design  
SEQRA Compliance  
Sewage & Drainage  
Topographic & Site Surveys

